Company: **Siemens Energy, Inc.**
Office Address: 15F NEX Tower, 6786 Ayala Ave. San Lorenzo Makati City
Email Address: arvin.adarlo@siemens-energy.com

Page / Section Number	Discussion of Comment(s) and/or Questions for Clarification	Comment/s and Suggestion/s
Annex A, Items A.1 / O.1; Sec. 19	The draft appears to use ISO conditions as the basis for reference ratings and heat-rate caps. For project evaluation purposes, stakeholders would benefit from understanding how the Commission intends to account for site-specific conditions, particularly since actual Philippine operating conditions may differ from ISO reference conditions.	May we request the Commission to clarify whether the ISO-based values are intended only on a common reference basis, or whether adjustments to site-specific net output and heat-rate values will be considered.
Annex A, Item A.2, Reference Net Capacity Factor	The reference capacity factor is stated as "to be determined by the Commission." The assumed capacity factor is important because the operating profile of a mid-merit facility can influence technology configuration, maintenance planning, and long-term service strategy.	May we request the Commission to clarify the intended capacity factor range for the reference mid-merit facility. The expected operating profile would help assess suitable technology configurations and service concepts that can support the intended mid-merit operation.
Annex A, Items A.4 and A.5, Fixed and Variable O&M	The draft references O&M assumptions derived from the FGP San Lorenzo PPA and escalated to current price levels.	May we request the Commission to provide additional context on the applicability of the selected O&M benchmark across different plant configurations. As different equipment and operators have different operation modes, O&M facility set up and maintenance agreements with their respective OEMs.

Annex A, Items A.5 / O.5, Start-up Fuel and Cycling	The draft includes start-up fuel and cycling-related assumptions. For a mid-merit facility, the expected number of starts, operating cycles, and dispatch pattern may materially influence operating strategy and maintenance planning.	May we request how the single start up fuel cost was derived by the Commission and the related cycling assumptions.
Sec. 19 / Annex A, Item A.15, Reference Heat Rate Cap	The draft provides that Reference Heat Rate caps will be determined consistent with commercially available technology, and that fuel consumption above the cap cannot be passed through.	May we request the Commission to clarify which references were used for setting Reference Heat Rate caps.
Annex A, Item O.1, OCGT Reference Plant	The draft cites a Siemens SGT5-4000F-class reference for the OCGT category. The draft may also benefit from recognizing that OCGT and CCGT configurations can be achieved through different commercially available gas turbine arrangements, including modular configurations.	We respectfully suggest that the Commission consider updating or clarifying Siemens Energy's reference technology to the equivalent 60 Hz platform (SGT6-4000F), as the cited SGT5-4000F is a 50 Hz machine. We further suggest that the framework recognizes the availability of commercially proven gas turbine solutions across different capacity ranges and configurations, including SGT6-8000H, SGT6-9000HL-class technologies for large-scale applications and SGT-800 class technologies that may be deployed in either open-cycle or combined-cycle configurations.
Annex A, Items O.3 to O.5, OCGT Scaling Ratios	The draft applies scaling ratios for OCGT relative to the CCGT reference, including CAPEX, Fixed O&M, and Variable O&M assumptions.	We respectfully request the Commission to provide further information on the basis for the OCGT scaling ratios.